

AD-A103 755

NEW JERSEY DEPT OF ENVIRONMENTAL PROTECTION TRENTON --ETC F/6 13/13
NATIONAL DAM SAFETY PROGRAM, CARPI LAKE DAM (NJ 00192) PASSAIC --ETC(U)
JUL 81 W A GUINAN DACW61-79-C-0011

UNCLASSIFIED

DAEN/NAP-53842/NJ00192-81/ NL

1 OF 1
AD-A
103 755



END
DATE
FILMED
10-81
DTIC

LEVEL II

0

AD A103755

PASSAIC RIVER BASIN,
TRIBUTARY TO MORSETOWN BROOK,
PASSAIC COUNTY
NEW JERSEY.

CARPI LAKE DAM
(NJ 00192)

PHASE 1 INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM.



APPROVED FOR PUBLIC RELEASE;
DISTRIBUTION UNLIMITED.

DEPARTMENT OF THE ARMY

Philadelphia District
Corps of Engineers
Philadelphia, Pennsylvania

DTIC
ELECTE

SEP 4 1981

S

D

JULY 1981

D

REPT. NO: DAEN(WAP- 53842/NJ 00192 - 81/07

81 9 03 068

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER DAEN/NAP 53842/NJ00192-81/07	2. GOVT ACCESSION NO. AD-A103755	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Phase I Inspection Report National Dam Safety Program Carpi Lake Dam, NJ00192 Passaic County, New Jersey	5. TYPE OF REPORT & PERIOD COVERED 9 FINAL rept.	
7. AUTHOR(s) Guinan, Warren P. E. ⑩ Warren A. Guinan	8. CONTRACT OR GRANT NUMBER(s) DACW61-79-C-0011 ✓	
9. PERFORMING ORGANIZATION NAME AND ADDRESS Anderson-Nichols 150 Causeway St. Boston, Massachusetts 02114	10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS	
11. CONTROLLING OFFICE NAME AND ADDRESS NJ Department of Environmental Protection Division of Water Resources P.O. Box CNO29 Trenton, NJ 08625	12. REPORT DATE Jul 81	
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) U.S. Army Engineer District, Philadelphia Custom House, 2d & Chestnut Streets Philadelphia, PA 19106 ⑪ 741	13. NUMBER OF PAGES 50	
	15. SECURITY CLASS. (of this report) Unclassified	
	15a. DECLASSIFICATION/DOWNGRADING SCHEDULE	
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in file) National Dam Safety Program. Carpi Lake Dam (NJ 00192) Passaic River Basin, Tributary to Morsetown Brook, Passaic County, New Jersey. Phase I Inspection Report.		
18. SUPPLEMENTARY NOTES Copies are obtainable from National Technical Information Service, Springfield, Virginia 22151.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dams Embankments Visual Inspection Structural Analysis National Dam Safety Program Carpi Lake Dam, N.J. Spillways Erosion		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report cites results of a technical investigation as to the dam's adequacy. The inspection and evaluation of the dam is as prescribed by the National Dam Inspection Act, Public Law 92-367. The technical investigation includes visual inspection, review of available design and construction records, and preliminary structural and hydraulic and hydrologic calculations, as applicable. An assessment of the dam's general condition is included in the report. → page 2		



DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
CUSTOM HOUSE-2 D & CHESTNUT STREETS
PHILADELPHIA, PENNSYLVANIA 19106

IN REPLY REFER TO

NAPEN-N

31 AUG 1981

Honorable Brendan T. Byrne
Governor of New Jersey
Trenton, New Jersey 08621

Dear Governor Byrne:

Inclosed is the Phase I Inspection Report for Carpi Lake Dam in Passaic County, New Jersey which has been prepared under authorization of the Dam Inspection Act, Public Law 92-367. A brief assessment of the dam's condition is given in the front of the report.

Based on visual inspection, available records, calculations and past operational performance, Carpi Lake Dam, initially listed as a high hazard potential structure, but reduced to a significant hazard potential structure as a result of this inspection, is judged to be in poor overall condition. The dam's spillway is considered inadequate because a flow equivalent to 47 percent of the Spillway Design Flood - SDF - would cause the dam to be overtopped. (The SDF, in this instance, is one half of the Probable Maximum Flood). To ensure adequacy of the structure, the following actions, as a minimum, are recommended:

a. The spillway's adequacy should be determined by a qualified professional consultant engaged by the owner using more sophisticated methods, procedures and studies within six months from the date of approval of this report. Within three months of the consultant's findings remedial measures to ensure spillway adequacy should be initiated.

b. Within one year from the date of approval of this report the owner should engage a qualified professional consultant to perform the following:

(1) Investigate the cause of wet, soft areas and standing water at the downstream toe of the dam.

(2) Investigate the uneven condition of the dam crest and design or specify measures to correct this condition.

(3) Design or specify the repairs for the erosion of the upstream slope and oversee the placement of adequate erosion protection for the upstream slope of the dam.

APPROVED FOR PUBLIC RELEASE;
DISTRIBUTION UNLIMITED.

NAPEN-N

Honorable Brendan T. Byrne

(4) Specify and oversee removal of trees, brush and vines from the entire embankment.

(5) Design and oversee replacement of the collapsed right, downstream concrete spillway training wingwall.

(6) Design and oversee the placement of adequate erosion protection along the toe of the embankment adjacent to the discharge channel.

(7) Design and oversee repairs to deteriorated concrete on the spillway and low-level outlet valve pit.

c. Within six months from the date of approval of this report the following remedial actions should be initiated:

(1) Start a program of periodically checking the condition of the dam and monitoring the wet area along the toe of the downstream slope.

(2) Remove trees and brush for a distance of 25 feet downstream from the toe of the dam or to the property line, whichever is less.

(3) Control trespassing on the dam.

d. Within one year from the date of approval of this report the following remedial actions should be initiated:

(1) Re-establish and maintain grassy vegetation on the dam after removal of trees, brush, vines and repair of eroded areas on the dam.

(2) Clear trees and brush on either side of the spillway discharge channel for distance of 100 feet from the spillway crest or to the limits of the property line whichever is less.

(3) Clean and paint all rusted steel on the service bridge.

(4) Repair or replace steel ladder in valve pit.

e. The owner should develop written operating procedures and a periodic maintenance plan to ensure the safety of the dam, within one year from the date of approval of this report.

f. An emergency action plan and warning system should be developed which outlines actions to be taken by the owner to minimize the downstream effects of an emergency at the dam within six months from the date of approval of this report.

A copy of the report is being furnished to Mr. Dirk C. Hofman, New Jersey Department of Environmental Protection, the designated State Office contact for this program. Within five days of the date of this letter, a copy will also be sent to Congressman Roe of the Eighth District. Under the provision of the Freedom of Information Act, the inspection report will be subject to release by this office, upon request, five days after the date of this letter.

NAPEN-N

Honorable Brendan T. Byrne

Additional copies of this report may be obtained from the National Technical Information Services (NTIS), Springfield, Virginia 22161 at a reasonable cost. Please allow four to six weeks from the date of this letter for NTIS to have copies of the report available.

An important aspect of the Dam Inspection Program will be the implementation of the recommendations made as a result of the inspection. We accordingly request that we be advised of proposed actions taken by the State to implement our recommendations.

Sincerely,



ROGER L. BALDWIN

Lieutenant Colonel, Corps of Engineers
Commander and District Engineer

1 Incl

As stated

Copies furnished:

Mr. Dirk C. Hofman, P.E., Deputy Director
Division of Water Resources
N.J. Dept. of Environmental Protection
P.O. Box CN029
Trenton, NJ 08625

Mr. John O'Dowd, Acting Chief
Bureau of Flood Plain Regulation
Division of Water Resources
N.J. Dept. of Environmental Protection
P.O. Box CN029
Trenton, NJ 08625

Accession For	
NTIS GRA&I	<input checked="checked" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
FI	

CARPI LAKE DAM (NJ00192)

CORPS OF ENGINEERS ASSESSMENT OF GENERAL CONDITIONS

This dam was inspected on 23 April 1981 by Anderson-Nichols and Co. Inc., under contract to the State of New Jersey. The State, under agreement with the U.S. Army Engineer District, Philadelphia, had this inspection performed in accordance with the National Dam Inspection Act, Public Law 92-367.

Carpi Lake Dam, initially listed as a high hazard potential structure, but reduced to a significant hazard potential structure as a result of this inspection, is judged to be in poor overall condition. The dam's spillway is considered inadequate because a flow equivalent to 47 percent of the Spillway Design Flood - SDF - would cause the dam to be overtopped. (The SDF, in this instance, is one half of the Probable Maximum Flood). To ensure adequacy of the structure, the following actions, as a minimum, are recommended:

a. The spillway's adequacy should be determined by a qualified professional consultant engaged by the owner using more sophisticated methods, procedures and studies within six months from the date of approval of this report. Within three months of the consultant's findings remedial measures to ensure spillway adequacy should be initiated.

b. Within one year from the date of approval of this report the owner should engage a qualified professional consultant to perform the following:

(1) Investigate the cause of wet, soft areas and standing water at the downstream toe of the dam.

(2) Investigate the uneven condition of the dam crest and design or specify measures to correct this condition.

(3) Design or specify the repairs for the erosion of the upstream slope and oversee the placement of adequate erosion protection for the upstream slope of the dam.

(4) Specify and oversee removal of trees, brush and vines from the entire embankment.

(5) Design and oversee replacement of the collapsed right, downstream concrete spillway training wingwall.

(6) Design and oversee the placement of adequate erosion protection along the toe of the embankment adjacent to the discharge channel.

(7) Design and oversee repairs to deteriorated concrete on the spillway and low-level outlet valve pit.

c. Within six months from the date of approval of this report the following remedial actions should be initiated:

(1) Start a program of periodically checking the condition of the dam and monitoring the wet area along the toe of the downstream slope.

(2) Remove trees and brush for a distance of 25 feet downstream from the toe of the dam or to the property line, whichever is less.

(3) Control trespassing on the dam.

d. Within one year from the date of approval of this report the following remedial actions should be initiated:

(1) Re-establish and maintain grassy vegetation on the dam after removal of trees, brush, vines and repair of eroded areas on the dam.

(2) Clear trees and brush on either side of the spillway discharge channel for distance of 100 feet from the spillway crest or to the limits of the property line whichever is less.

(3) Clean and paint all rusted steel on the service bridge.

(4) Repair or replace steel ladder in valve pit.

e. The owner should develop written operating procedures and a periodic maintenance plan to ensure the safety of the dam, within one year from the date of approval of this report.

f. An emergency action plan and warning system should be developed which outlines actions to be taken by the owner to minimize the downstream effects of an emergency at the dam within six months from the date of approval of this report.

APPROVED:



ROGER L. BALDWIN
Lieutenant Colonel, Corps of Engineers
Commander and District Engineer

DATE:

31 Aug 51

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

Name of Dam:	Carpi Lake
Identification No.:	Fed ID No. NJ00192
State Located:	New Jersey
County Located:	Passaic
Stream:	Morsetown Brook
River Basin:	Passaic
Date of Inspection:	April 23, 1981

ASSESSMENT OF GENERAL CONDITIONS


Carpi Lake Dam is about 50 years old and is in poor condition. The dam is 300 feet long, 12.1 feet high, and about 20 feet wide. The dam is small and its hazard classification is significant. The earthen embankment contains a central axial concrete core wall, a 12-inch low-level outlet with valve box cast integrally with the core wall, and a 25-foot ogee spillway located near the left abutment. The downstream slope is covered with vines, brush, and trees and the area downstream of the toe is generally wet and soft. The retreat channel runs along the downstream toe for about 50 feet. The right side training wingwall from the spillway has collapsed into the channel exposing the embankment and dumped riprap. The upstream slope, with several trees growing at or above the waterline, shows evidence of erosion and displacement of riprap at and above the waterline. The grass covered dam crest is rather uneven. Several roots of trees extend the entire width of the crest. The spillway's crest has some minor spalling of concrete and a small crack near the toe. The spillway is capable of passing 46 percent of the selected spillway design flood inflow hydrograph of one-half PMF (652 cfs) and is considered inadequate.

The owner should engage a professional engineer, qualified in the design and construction of dams to accomplish the following in the near future: evaluate further the adequacy of the spillway capacity and design and oversee construction of additional capacity, if found necessary; investigate the cause of wet, soft areas and standing water at the downstream toe of the dam; investigate the uneven condition of the dam crest and design or specify remedial measures to correct the condition; design or specify the repairs for the erosion of the upstream slope and oversee the placement of adequate erosion protection for the upstream slope of the dam; specify and oversee removal of trees, brush and vines from the entire embankment; design and oversee replacement of the collapsed right, downstream concrete training wingwall; design and oversee the placement of adequate erosion protection along the toe of the embankment adjacent to the discharge channel; design and oversee repairs to deteriorated concrete on the spillway and low-level outlet valve pit.

It is further recommended that the owner accomplish the following tasks as part of operational and maintenance procedures. Beginning soon: start a program of periodically checking the condition of the dam and monitoring the wet area along the toe of the downstream slope; develop an emergency action plan which outlines actions taken by the owner to minimize downstream effects of an emergency at the dam; remove trees and brush for a distance of 25 feet downstream from the toe of the dam or to the property line, whichever is less; control trespassing on the dam. In the near future: re-establish and maintain grassy vegetation on the dam embankment; clear trees and brush on either side of the spillway discharge channel for a distance of 100 feet from the spillway crest or to the limits of the property line, whichever is less; clear and paint all rusted steel on the service bridge; repair or replace steel ladder in valve pit; and develop written operating procedures and a periodic maintenance plan to ensure the safety of the dam.

ANDERSON-NICHOLS & COMPANY, INC.

Warren A. Guinan
Warren A. Guinan, P.E.
Project Manager
New Jersey 16848



April 23, 1981

OVERVIEW PHOTO
CAPRI LAKE DAM

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test Flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonable possible storm runoff), or fractions thereof. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

CONTENTS

PHASE I INSPECTION REPORT NATIONAL DAM SAFETY REPORT

CARPI LAKE DAM FED ID NO. NJ00192

		<u>Page</u>
SECTION 1	PROJECT INFORMATION	
	1.1 <u>General</u>	1
	1.2 <u>Project Description</u>	1
	1.3 <u>Pertinent Data</u>	3
SECTION 2	ENGINEERING DATA	
	2.1 <u>Design</u>	5
	2.2 <u>Construction</u>	5
	2.3 <u>Operation</u>	5
	2.4 <u>Evaluation</u>	5
SECTION 3	VISUAL INSPECTION	6
SECTION 4	OPERATIONAL PROCEDURES	
	4.1 <u>Procedures</u>	8
	4.2 <u>Maintenance of Dam</u>	8
	4.3 <u>Maintenance of Operating Facilities</u>	8
	4.4 <u>Warning System</u>	8
	4.5 <u>Evaluation of Operational Adequacy</u>	8
SECTION 5	HYDRAULIC/HYDROLOGIC	9
SECTION 6	STRUCTURAL STABILITY	10
SECTION 7	ASSESSMENT, RECOMMENDATIONS/REMEDIAL MEASURES	
	7.1 <u>Assessment</u>	12
	7.2 <u>Recommendations/Remedial Measures</u>	12
FIGURES	1. Regional Vicinity Map	
	2. Essential Project Features	
APPENDICES	1. Check List Visual Inspection	
	2. Photographs	
	3. Hydrologic Computations	
	4. HEC-1 Output	
	5. References	

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY INSPECTION PROGRAM
CARPI LAKE DAM
FED ID NO. #NJ00192

SECTION 1
PROJECT INFORMATION

1.1 General

a. Authority. Authority to perform the Phase I Safety Inspection of Carpi Lake Dam was received from the State of New Jersey, Department of Environmental Protection, Division of Water Resources by letter dated 12 December 1980 under Basic Contract No. FPM-39 and Contract No. A01093 dated 10 October, 1979. This Authority was given pursuant to the National Dam Inspection Act, Public Law 92-367 and by agreement between the State and the U.S. Army Engineers District, Philadelphia. The inspection discussed herein was performed by Anderson-Nichols & Company, Inc.

b. Purpose: The purpose of the Phase I Investigation is to develop an assessment of the general conditions with respect to the safety of Carpi Lake Dam and appurtenances. Conclusions are based upon available data and visual inspection. The results of this study were used to determine any need for emergency measures and to conclude if additional studies, investigations, and analyses are necessary and warranted.

1.2 Project Description

a. Description of Dam and Appurtenances. Carpi Lake Dam is a 300-foot long, 12.1-foot high earthfill dam with a concrete core wall. The dam crest is approximately 20 feet wide; the slopes are 3H:1V on the upstream side and 2H:1V on the downstream side. The ogee spillway is 25 feet long, 16 feet wide including the downstream apron, and 8.5 feet high. The spillway has concrete abutment training walls and is located on the left (west) side of the dam. A concrete slab bridge crosses the spillway.

b. Location. Carpi Lake Dam is located on Morsetown Brook in West Milford Township, Passaic County, New Jersey. The dam is at 41° 06.7' north latitude 74° 21.3' west longitude on the Wanaque Quadrangle. To reach the dam from the nearby township of West Milford go east from the center of town on Marshall Hill Road. Turn right and proceed south for approximately 1 mile on Morsetown Road. Carpi Lake is on the right (west) side of the road. A location map has been included as Figure 2.

c. Size Classification. Carpi Lake Dam is classified as being small in size on the basis of storage at top of dam of 83 acre-feet, which is less than 1000 acre-feet but more than 50 acre-feet, and on the basis of its structural height of 12.1 feet, which is less than 40 feet, in accordance with criteria given in the Recommended Guidelines for Safety Inspection of Dams.

d. Hazard Classification. Downstream of Carpi Lake Dam are two small ponds. Morsetown Road crosses Morsetown Brook, the downstream channel, between the two ponds. Around the second pond are several houses whose back porches are approximately 6 feet above the water. If the dam were overtopped, Morsetown Road could possibly be damaged and minor flooding might occur at 4 to 6 houses around the second downstream pond. Damage to Morsetown Road would probably be appreciable; but few, if any, lives would be lost. Therefore, Carpi Lake Dam is given a significant hazard classification.

e. Ownership. The dam is owned by Helen Iafrate, West Milford, New Jersey 07480; for information she may be reached at the above address.

f. Purpose. The dam impounds a lake which is used for recreational purposes.

g. Design and Construction History. According to the owner, the dam was constructed between 1929-1939 and designed by Caesar Carpiniano. Plans for the dam were found in the files of the New Jersey Department of Environmental Protection, 1474 Prospect Street, Trenton, New Jersey 08625. However, no hydraulic or hydrologic data were discovered.

h. Normal Operational Procedure. No operational procedures exist for the dam.

i. Site Geology. No site specific geologic information (such as borings) was available at the time the dam was inspected. Information derived from the Geologic Map of New Jersey (Kummel and Lewis, 1912) and the Glacial Drift Map of New Jersey (Salisbury, Kummel, Peet and Whitson, 1902) indicates that soils within the immediate site area consist of ground moraine overlying bedrock. Bedrock was observed in several outcrops at the left side of the downstream channel during inspection of this dam. The previously mentioned map indicates that bedrock in this area consists of granitoid gneiss of Precambrian age.

1.3 Pertinent Data

a. Drainage Area

.28 square miles

b. Discharge at Damsite (cfs)

Maximum flood at damsite - unknown

Total ungated spillway capacity at maximum pool
(top of dam) elevation - 205

c. Elevation (ft. above NGVD)

Top of dam - 937.4

Maximum pool test flood - (1/2 PMF) - 938.4

Recreation pool (at time of inspection) - 935.8

Spillway crest - 935.7

Streambed at centerline of spillway - 927.2

Maximum tailwater - (estimated) 928.5

d. Reservoir (feet)

Length of maximum pool - 3000 (estimated)

Spillway crest - 1400

e. Storage (acre-feet)

Spillway crest - 57

Top of dam - 83

Test Flood - (1/2 PMF) - 100

f. Reservoir Surface (acres)

Top of dam - 19 (estimated)

Spillway crest - 12.8

g. Dam

Type - earthfill with concrete corewall and spillway

Length - 300 feet

Height - 10.2 feet (hydraulic),
- 12.1 feet (structural)

Top width - 20 feet

Side slopes - upstream 3H:1V, downstream 2H:1V

Zoning - unknown

Impervious core - concrete

Cutoff - unknown

Grout curtain - unknown

h. Spillway

Type - Ogee

Length of weir - 25 feet

Crest elevation - 935.7' NGVD

Low level outlet - 12-inch C.I.P.

U/S Channel - Carpi Lake

D/S Channel - Morsetown Brook

i. Low-Level Outlet

Size - 12-inch C.I.P.

Access - Valve box near spillway, centered on corewall

Upstream invert elevation - 927.2 (est.)

Downstream invert elevation - 927.0 (est.)

SECTION 2 ENGINEERING DATA

2.1 Design

The original plans for Carpi Lake Dam are on file at the New Jersey Department of Environmental Protection, 1474 Prospect Street, Trenton, New Jersey 08625. According to the owner of the dam, Ms. Helen Iafrate, the dam was designed by Caesar Carpiniano. No hydraulic or hydrologic engineering data were disclosed.

2.2 Construction

No recorded data concerning the original construction of Carpi Lake Dam were revealed.

2.3 Operation

No data pertaining to the operation of the dam were disclosed.

2.4 Evaluation

a. Availability. A search of the New Jersey Department of Environmental Protection files and contact with the owner and community officials revealed no other pertinent information except for the plan of the dam.

b. Adequacy. Evaluation was based primarily on visual observations which are deemed adequate for this Phase I inspection.

SECTION 3 VISUAL INSPECTION

3.1 Findings

a. Dam. The downstream slope of the dam is covered with a very dense growth of trees, brush, vines, and miscellaneous debris which makes it impossible to inspect the downstream slope adequately. The right concrete training wing wall of the spillway, which is 15 feet long, has collapsed into the discharge channel immediately downstream from the spillway exposing the embankment soils. The downstream slope is covered with dumped riprap from the crest to the toe adjacent to the downstream end of the collapsed concrete training wing wall. At one location to the left of the service bridge over the spillway is a footpath which is mostly bare of vegetation from the crest to the toe of the slope.

The crest of the dam is rather uneven and mostly covered with grass. Several trees are growing at or above the waterline on the upstream slope. Several large roots were observed extending the entire width of the crest. Considerable erosion has occurred on the upstream slope at and above the waterline resulting in displacement of several sections of riprap.

The area downstream of the toe of the dam is covered with trees, vines, and brush and is generally wet and soft. Some standing water was noted downstream of the dam but no evidence of flowing water was observed. Several trees have blown over downstream of the toe.

The top of the concrete corewall is spalled and eroded. No evidence of major thru wall cracking or movement was noted.

b. Appurtenant Structures.

- (1) Ungated Spillway. The downstream face of the spillway in the vicinity of the 2-inch notch in the crest is surface eroded approximately 3/4 of an inch exposing the coarse aggregate. A wet spot on the downstream face was visible near the bottom left end. The concrete abutments at the end of the spillway are eroded at the waterline upstream of the spillway. A large section of the right concrete spillway training wing wall has collapsed adjacent to the spillway (See Section 3.1.a above).

- (2) Service Bridge. The steel beams are surface corroded and the center piers are rusting where they have been in contact with water. The upstream edge of the concrete deck is spalled and eroded.
- (3) Low Level Outlet. A crack runs the full height of the low-level outlet valve pit on both sides. The steel stairs in the pit are badly corroded, and the downstream end of the outlet pipe is covered with debris and could not be seen.

c. Reservoir Area. The watershed above the lake is gently to moderately sloping and wooded. Morsetown Road runs parallel to the east edge of the reservoir. The reservoir slopes appear to be stable. No evidence of significant sedimentation was observed in the reservoir. Several trees are overhanging the pond at the approach to the spillway at the left abutment.

d. Downstream Channel. The channel downstream from the spillway runs along the toe of the embankment for about 50 feet before making a turn downstream. Considerable erosion has occurred on the right and left banks of the channel immediately downstream of the spillway for a distance of 100 to 200 feet. The channel bottom is in soil and there is limited erosion protection on the side of the channel adjacent to the toe.

SECTION 4
OPERATIONAL PROCEDURES

4.1 Procedures

No formal operating procedures were disclosed. Water level is controlled as the situation dictates.

4.2 Maintenance of Dam

No formal maintenance procedures for the dam were disclosed.

4.3 Maintenance of Operating Facilities

No formal maintenance procedures for the operating facilities were disclosed. The owner said that she opens the drawdown line to lower the water level about 2 feet each fall and allows spring freshets to refill the reservoir.

4.4 Warning System

No description of any warning system was found.

4.5 Evaluation of Operational Adequacy

Because of the lack of operation and maintenance procedures, the remedial measures described in Section 7.2 should be implemented as prescribed.

SECTION 5
HYDROLOGIC/HYDRAULIC

5.1 Evaluation of Features

a. Design Data. Because no hydrologic or hydraulic data were revealed, an evaluation could not be performed.

b. Experience Data. No experience data were found.

c. Visual Inspection. The ogee spillway is, in general, in good condition with minor crest spalling and a wet spot on the ogee face. The right downstream training wall of the spillway has collapsed. The owner states that this big block of concrete now serves in part as an energy dissipator on the right side. However, the embankment is exposed and is ravelling behind the overturned wingwall. Vertical cracks were noted in the walls of the valve box, and its steel access ladder was badly corroded. The downstream outlet of the drawdown pipe was covered with debris and the outlet was not observed. The downstream channel empties into a small dammed pond about 100 yards downstream of the dam. The channel downstream from this low dam runs through a 3 x 4 foot box culvert under Morsetown Road and empties into a second small pond. Several houses have their first floor 6 feet above the normal water surface of this second pond.

d. Carpi Lake Dam Overtopping Potential. The hydraulic/hydrologic evaluation for the dam is based on a selected Spillway Design Flood (SDF) equal to one-half the probable maximum flood (PMF) in accordance with the range of test floods given in the evaluation guidelines for dams classified as significant hazard and small in size. The PMF was determined by application of the SCS dimensionless unit hydrograph to a 24-hour probable maximum precipitation of 22.0 inches. Hydrologic computations are given in Appendix 3.

The one-half PMF peak inflow to the reservoir is 870 cfs. The routed, one-half PMF discharge from the reservoir is 637 cfs.

The minimum elevation of the top of dam allows 1.7 feet of depth above the spillway. Under this head the total spillway capacity is 205 cfs, which is capable of passing 46 percent of the selected SDF inflow hydrograph. Thus the spillway is considered inadequate.

Flood routing calculations indicate that Carpi Lake Dam will be overtopped for 3 hours to a maximum depth of 0.9 foot under one-half PMF conditions.

e. Drawdown Capability. The 12-inch low-level outlet is capable of dewatering the dam in about 4 days, assuming no inflow; this is considered adequate.

SECTION 6 STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability

The presence of a dense growth of trees, vines, miscellaneous debris, and brush on the downstream slope of the embankment makes it impossible to make an adequate visual inspection of the embankment.

Trees growing on the embankment and in the area downstream of the toe may blow over and pull out their roots, or they may die with the result that the roots rot. Either of these events may result in serious seepage and erosion problems.

The collapse of the right concrete spillway training wall and adjacent erosion along the embankment toe that is due to the flow of water in the discharge channel could lead to a breach of the embankment and could also contribute to stability problems in the spillway structure.

The pedestrian path to the left of the spillway, mostly bare of vegetation from the crest to the downstream toe of the embankment, is susceptible to additional erosion and consequent damage to the embankment due to both runoff of rainfall and, if it should occur, overtopping.

The crest of the dam is uneven. Although the cause of the unevenness cannot be determined on the basis of visual inspection alone, it may be a sign of a potential stability problem. The soft, wet area and standing water at the downstream toe of the dam may be indicative of seepage through and under the dam which, if not properly controlled, could lead to failure of the dam by piping or sloughing of the downstream slope.

The deteriorating concrete in the spillway and the cracks in the valve pit box (because it is on the core wall) could contribute to stability problems if allowed to advance.

Serious erosion of the upstream slope of the dam at and above the waterline, if allowed to continue, could result in eventual breaching of the embankment.

6.2 Design and Construction Data

No design or construction data pertinent to the structural stability of the dam are available.

6.3 Operating Records

No operating records pertinent to the structural stability of the dam were available.

6.4 Post-Construction Changes

No record of post-construction changes was available.

6.5 Seismic Stability

This dam is in Seismic Zone 1. According to the Recommended Guidelines, dams located in Seismic Zone 1 "may be assumed to present no hazard from earthquake provided static stability conditions are satisfactory and conventional safety margins exist." The observations made during the visual inspection provided an indication of unstable embankments as mentioned in Section 6.1. However, because no data are available concerning the engineering properties of the embankment and foundation materials for this dam or the condition at the base of the core wall, it is not possible to make an engineering evaluation of the stability of the slope or the factor of safety under static conditions.

SECTION 7
ASSESSMENT, RECOMMENDATIONS/REMEDIAL MEASURES

7.1 Dam Assessment

a. Condition. Carpi Dam is approximately 50 years old and is in poor condition.

b. Adequacy of Information. The information available is such that the assessment of the dam must be based primarily on the results of the visual inspection.

c. Urgency. The recommendations made in 7.2.a and 7.2.b should be implemented by the owner as prescribed.

d. Necessity for Additional Data/Evaluation. The information available from the visual inspection is adequate to identify the potential problems which are listed in 7.2.a. These problems require the attention of a professional engineer who will have to make additional engineering studies to design or specify remedial measures to rectify the problems. If left unattended, the problems could lead to failure of the dam.

7.2 Recommendations/Remedial Measures

a. Recommendations.

The owner should engage a professional engineer qualified in the design and construction of dams to accomplish the following in the near future:

- (1) Evaluate further the adequacy of the spillway capacity and design and oversee construction of additional capacity if found necessary.
- (2) Investigate the cause of wet, soft areas and standing water at the downstream toe of the dam.
- (3) Investigate the uneven condition of the dam crest and design or specify measures to correct this condition.
- (4) Design or specify the repairs for the erosion of the upstream slope and oversee the placement of adequate erosion protection for the upstream slope of the dam.
- (5) Specify and oversee removal of trees, brush and vines from the entire embankment.

- (6) Design and oversee replacement of the collapsed right, downstream concrete spillway training wingwall.
- (7) Design and oversee the placement of adequate erosion protection along the toe of the embankment adjacent to the discharge channel.
- (8) Design and oversee repairs to deteriorated concrete on the spillway and low-level outlet valve pit.

b. Alternatives. No alternative measures are recommended unless the owner determines that the reservoir is no longer required. In that case, the dam may be breached.

c. Operating and Maintenance Procedures.


The owner should accomplish the following soon:

- (1) Start a program of periodically checking the condition of the dam and monitoring the wet area along the toe of the downstream slope.
- (2) Develop an emergency action plan which outlines actions taken by the owner to minimize downstream effects of an emergency at the dam.
- (3) Remove trees and brush for a distance of 25 feet downstream from the toe of the dam or to the property line, whichever is less.
- (4) Control trespassing on the dam.


In the near future:

- (1) Re-establish and maintain grassy vegetation on the dam after removal of trees, brush, vines and repair of eroded areas on the dam.
- (2) Clear trees and brush on either side of the spillway discharge channel for distance of 100 feet from the spillway crest or to the limits of the property line whichever is less.
- (3) Clean and paint all rusted steel on the service bridge.
- (4) Repair or replace steel ladder in valve pit.
- (5) Develop written operating procedures and a periodic maintenance plan, to ensure the safety of the dam.

CARPI LAKE



PLAN



ELEVATION

12" C.I.P.
INVERT El. 927.2

Anderson-Nichols & Co., Inc.		U.S. ARMY ENGINEER DIST PHILADELPHIA	
BOSTON		CORPS OF ENGINEERS	
MASSACHUSETTS		PHILADELPHIA, PA	
NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS			
CARPI LAKE DAM			
TRIB. TO MORSETOWN BROOK		NEW JERSEY	
		SCALE NOT TO SCALE	
		DATE JUNE 1981	

FIGURE -1



SCALE IN MILES



MAP BASED ON STATE OF NEW JERSEY
OFFICIAL MAP & GUIDE.

Anderson-Nichols & Co., Inc.

BOSTON

MASSACHUSETTS

U.S. ARMY ENGINEER DIST. PHILADELPHIA
CORPS OF ENGINEERS
PHILADELPHIA, PA.

NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS

CARPI LAKE DAM LOCATION MAP

TRIB. TO MORSETOWN BROOK

NEW JERSEY

SCALE: 1" = 4 Miles Approx.

DATE: JUNE 1981

FIGURE

APPENDIX 1

CHECK LIST

VISUAL INSPECTION

CARPI LAKE DAM

Check List
Visual Inspection
Phase 1

Name Dam Carpi Lake Dam County Passaic State NJ (00192) Coordinators NJDEP
 Date(s) Inspection 2/17/81 4/23/81 Weather' Sunny, warm Rain Temperature 52° 55°
 Pool Elevation at Time of Inspection 934.7' NGVD Tailwater at Time of Inspection None NGVD

Inspection Personnel:

W. Guinan

K. Stuart

C. Plaud

S. Gilman

D. Deane

R. Murdock

R. Murdock/K. Stuart Recorder

Owner did not accompany inspection party

UNGATED SPILLWAY

VISUAL EXAMINATION OF

OBSERVATIONS

REMARKS OR RECOMMENDATIONS

CONCRETE WEIR

Concrete in fair condition. Erosion of concrete surface in vicinity of 2-inch notch is eroded 3/4-inch exposing coarse aggregate. Face of spillway is surface eroded exposing coarse aggregate. Minor wet spot noted near bottom left of center.

Repair concrete

APPROACH CHANNEL

Clear - unobstructed

1-2

DISCHARGE CHANNEL

Brush, trees.
Training wall on right side d/s collapsed into channel about 4 years ago.
Natural stream bed, erosion on both banks.

Repair or replace training wall

BRIDGE AND PIERS OVER SPILLWAY

Concrete deck in fair condition. Piers in fair condition. Deck in good condition except for spalling and erosion on u/s edge. Abutments - both u/s faces are eroded and spalled at the water line and beneath the deck. Beams - Surface corroded - no paint. Columns - Painted but rusting where in contact with water - other minor areas of corrosion. Railing - fair - u/s railing is loose.

Repair deteriorated concrete.
Clean and paint rusting steel.
Repair railings.

EMBANKMENT

VISUAL EXAMINATION OF

OBSERVATIONS

REMARKS OR RECOMMENDATIONS

SURFACE CRACKS

None observed

UNUSUAL MOVEMENT OR
CRACKING AT OR BEYOND
THE TOE

None observed

SLOUGHING OR EROSION OF
EMBANKMENT AND ABUTMENT
SLOPES

Sloughing on upstream face, some trees,
sloughing and erosion on downstream
slope, extensive vegetation, difficult
to inspect slope thoroughly.

Clear vegetation; repair
erosion and provide adequate
erosion protection.

VERTICAL AND HORIZONTAL
ALIGNMENT OF THE CREST

Horizontal - Good
Vertical - Slight undulation of surface
near downstream edge of crest.

Investigate cause and correct
undulation.

RIPRAP FAILURES

Many areas of displaced riprap along crest.

Repair riprap.

EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
RAILINGS	None apparent	
JUNCTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND DAM	Erosion on both sides of spillway, right concrete spillway training wall collapsed downstream of spillway.	
ANY NOTICEABLE SEEPAGE	Entire toe wet and soggy, standing water evident, no seepage observed, may be obscured by extensive vegetation.	
STAFF GAGE AND RECORDER	None apparent	
DRAINS	None apparent	

OUTLET WORKS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CRACKING AND SPALLING OF CONCRETE SURFACES IN OUTLET CONDUIT	Crack running full height of concrete valve pit, both sides. Steel steps in chamber are badly corroded.	Repair cracks Replace steps
INTAKE STRUCTURE	Under ice - not visible	
OUTLET PIPE	Not visible, covered by brush and rocks, operated recently.	Remove brush and restore end of pipe.
OUTLET CHANNEL	Brush	
EMERGENCY GATE	Approximate 10-inch gate valve with hand wheel.	Verify operating capability of valve.

RESERVOIR

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
-----------------------	--------------	----------------------------

SLOPES

Gradual to steeply sloped, some open fields.

SEDIMENTATION

No appreciable sedimentation noted in reservoir.

DOWNSTREAM CHANNEL

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
-----------------------	--------------	----------------------------

CONDITION
(OBSTRUCTIONS,
DEBRIS, ETC.)

Brush filled, trees 6 inches to 8 inches

Cut trees/brush

SLOPES

Gentle slopes

APPROXIMATE NO.
OF HOMES AND
POPULATION

One house - 9-ft sill
One house - 12-ft sill
2 Houses - 3 ft above d/s pond
d/s bridge - 4 ft deep - 4.5 ft wide - 34 ft long

CHECK LIST
ENGINEERING DATA
DESIGN, CONSTRUCTION, OPERATION

ITEM	REMARKS
PLAN OF DAM	An undated plan, #22-129, is on file at the New Jersey Department of Environmental Protection, Prospect Street, Trenton, New Jersey 08625.
REGIONAL VICINITY MAP	Prepared for this report
CONSTRUCTION HISTORY	None found
TYPICAL SECTIONS OF DAM	See "PLAN OF DAM" above
HYDROLOGIC/HYDRAULIC DATA	None found
OUTLETS - PLAN	
- DETAILS	None found
- CONSTRAINTS	
- DISCHARGE RATINGS	
RAINFALL/RESERVOIR RECORDS	None found

ITEM	REMARKS
DESIGN REPORTS	None found
GEOLOGY REPORTS	None found
DESIGN COMPUTATIONS HYDROLOGY & HYDRAULICS DAM STABILITY SEEPAGE STUDIES	None found
MATERIALS INVESTIGATIONS BORING RECORDS LABORATORY FIELD	None found
POST-CONSTRUCTION SURVEYS OF DAM	None found
BORROW SOURCES	Unknown

ITEM	REMARKS
MONITORING SYSTEMS	None found
MODIFICATIONS	None found
HIGH POOL RECORDS	None found
POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS	None found
PRIOR ACCIDENTS OR FAILURE OF DAM DESCRIPTION REPORTS	None found
MAINTENANCE OPERATION RECORDS	None found

REMARKS

ITEMS

SPILLWAY PLAN See "PLAN OF DAM"

SECTIONS

DETAILS

OPERATING EQUIPMENT
PLANS & DETAILS

None found

CHECK LIST
HYDROLOGIC AND HYDRAULIC DATA
ENGINEERING DATA

DRAINAGE AREA CHARACTERISTICS: .28 square miles, woods

ELEVATION TOP NORMAL POOL (STORAGE CAPACITY): 935.7' NGVD (57.2 acre-
feet)

ELEVATION TOP FLOOD CONTROL POOL (STORAGE CAPACITY): Not applicable

ELEVATION MAXIMUM TEST FLOOD POOL: 938.4' NGVD

ELEVATION TOP DAM: 937.4' NGVD

SPILLWAY CREST: Overflow, low notch in weir

a. Elevation 935.7' NGVD

b. Type Ogee

c. Width 16 feet

d. Length 25 feet

e. Location Spillover Right end of dam

f. Number and Type of Gates None

OUTLET WORKS: 1-12" C.I.P., Invert at 927.2' NGVD

HYDROMETEOROLOGICAL GAGES: None

MAXIMUM NON-DAMAGING DISCHARGE: 205 cfs

APPENDIX 2

PHOTOGRAPHS

CARPI LAKE DAM



February 17, 1981

Bridge deck slab, core wall and valve box, looking from left (west) to right (east) along axis of dam.




February 17, 1981

Overflow spillway downstream face.



April 23, 1981

Erosion and spalling of concrete spillway training wall below bridge slab on upstream left side of dam.




April 23, 1981

Erosion adjacent to spillway, downstream left side.




April 23, 1981

Ogee spillway contact with left training wall. Note crack across face near bottom and wet spot near left bottom of photograph.



April 23, 1981

Beam anchorage under deck.



April 23, 1981

Collapsed right training wingwall of spillway;
rule extended 6 feet.




April 23, 1981

Undercutting at toe of slope caused by the close proximity
of discharge channel; looking upstream.



April 23, 1981

Crest is slightly undulating in elevation.




April 23, 1981

Large berm on downstream slope; may be due to former sloughing.



April 23, 1981

Ground wet and soggy with some standing water along toe of slope.




April 23, 1981

Large erosion feature at the toe of slope 3 feet wide, 4 feet along slope, and 2 feet deep.

APPENDIX 3
HYDROLOGIC COMPUTATIONS

CARPI LAKE DAM



**NATIONAL PROGRAM OF INSPECTION OF
NON - FED. DAMS**

**CARPI LAKE DAM
WEST MILFORD TOWNSHIP, NEW JERSEY
REGIONAL VICINITY MAP**


JUNE 1981

**DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA**

Anderson-Nichols & Company, Inc.

BOSTON, MA.

SCALE IN MILES



**MAP BASED ON U.S.G.S. 7.5 MINUTE QUADRANGLE
SHEET WANAQUE, N.J. 1954, REVISED 1971.**

JOB NO.

SQUARES
1/4 IN. SCALE

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30

Time of Concentration① Texas Highway Method

all overland - longest flowpath = 2,300 ft.

$$\text{Slope} = \frac{1100 - 935}{2,300} = 0.072 = 7.2\%$$

velocity = 2.0 fps for woodlands

$$\text{Time} = \frac{2,300}{2.0} = 1150 \text{ sec} = 0.32 \text{ hours}$$

② Soil and Water Conservation Method

$$L = 0.6 T_c = \frac{L^{0.8} (S+1)^{1.67}}{9,000 y^{0.5}} \quad S = \frac{1,000 - CN}{10}$$

$$y = 7.2\%$$

$$L = 2,300$$

$$CN = 70 \text{ for good condition woods, soil group C} \rightarrow S = 4.29$$

$$T_c = 0.55 \text{ hours}$$

③ Weston, or SCS T.R. #55 Method

all overland. Slope = 7.2%, length = 2,300 ft

From T.R. #55 graph, $v = 0.7$ fps

$$\text{Time} = \frac{2,300}{0.7} = 3,286 \text{ sec} = 0.91 \text{ hours}$$

④ Kerby Method

$$\text{all overland. } T_c = 0.83 \left(\frac{NL}{V_s^2} \right)^{0.467} \quad N = 0.7, L = 2,300 \text{ ft}, S = 0.072$$

$$T_c = 0.83 \left(\frac{0.7 (2,300)}{16.072} \right)^{0.467} = 48.2 \text{ min} = 0.80 \text{ hours}$$

JOB NO.

SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29
1/4 IN. SCALE1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40

Average of 4 methods: $T_c = \frac{0.32 + 0.55 + 0.91 + 0.80}{4} = 0.645 \text{ hours}$

$\text{lag} = 0.6 T_c = 0.387 \text{ hrs.}$

JOB NO.

SQUARES
1/4 IN. SCALE

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30

Stage Versus Discharge

A hydraulic profile of Carp Lake Dam is given on page 4. E = water surface elevation (feet above NGVD). Numbers in circles (①, ②, etc.) refer to sections numbered on page 4.

Spillway (section ③):

From 935.7 to about 938.5 weir flow, $Q = CLH^{3/2}$, $C = 3.7$ for ogee

$$Q = 3.7(25)(E - 935.7)^{3/2}$$

Above 938.5 or so, the spillway becomes an orifice with a broad-crested weir above.

$$Q = Q_{\text{orifice}} + Q_{\text{b.c. weir}}$$

$$= C_{\text{orifice}} A_{\text{orifice}} \sqrt{2gH_{\text{orifice}}} + C_{\text{weir}} L H_{\text{weir}}^{3/2}$$

$$C_{\text{orifice}} = 0.61$$

$$A_{\text{orifice}} = 25(2.4) = 60 \text{ ft}^2$$

$$H_{\text{orifice}} = E - 936.9$$

$$C_{\text{weir}} = 3.0$$

$$L = 25'$$

$$H_{\text{weir}} = E - 938.8$$

$$Q = 0.61(60) \sqrt{64.4} (E - 936.9)^{1/2} + 3.0(25)(E - 938.8)^{3/2}$$

$$= 293.7 (E - 936.9)^{1/2} + 3(25)(E - 938.8)^{3/2}$$

Top of Dam (sections ②, ④, ⑤, ⑥, ⑦, ⑧):

We will get stage vs. Q at 927.2, 935.7, 936, 936.5, 937, 937.4, 938, 938.5, 939, 939.5. $C = 2.7$ for all top of dam sections

JOB NO.

SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
1/4 IN. SCALE

Section ② is a 60H:1V sloping weir with avg. height 939.05, one end at 938.8, and the other at 939.3. Length = 30 ft.

Section ④ is a 45' long 32.1H:1V sloping weir with avg. height 938.1, one end at 937.4, and the other at 938.8


Section ⑤ is a 50' 250H:1V sloping weir, avg. ht. 937.5, ends 937.4 and 937.6

Section ⑥ is a 50' 500H:1V sloping weir, avg. ht. 937.65, ends 937.6 and 937.7

Section ⑦ is a 50' 250H:1V sloping weir, avg. ht. 937.8, ends 937.7 and 937.9

Section ⑧ is a 50' 83.3H:1V sloping weir, avg. ht. 938.2, ends 937.9 and 938.5

for a partially submerged sloping weir:




$$Q = C L_{\text{submerged}} H_{\text{avg}}^{3/2}$$

$$C_{\text{submerged}} = z (E_{\text{water}} - E_{\text{low}})$$

$$H_{\text{avg}} = \frac{0 + (E_{\text{water}} - E_{\text{low}})}{2} = 0.5(E_{\text{water}} - E_{\text{low}})$$

$$Q = C (z) (E_{\text{water}} - E_{\text{low}}) (0.5(E_{\text{water}} - E_{\text{low}}))^{3/2}$$

for a fully submerged sloping weir:



$$Q = C L H_{\text{avg}}^{3/2} = C L (E_{\text{water}} - E_{\text{avg}})^{3/2}$$

for stage of 927.2, 935.7, 936, 936.5, 937, 937.4: $Q = 0.0$

$$\begin{aligned} \text{for stage of } 938-938.5: Q = & 2.7 (32.1) (E-937.4) (0.5(E-937.4))^{3/2} + 2.7 (50) (E-937.5) (0.5(E-937.5))^{3/2} \\ & + 2.7 (50) (E-937.65) (0.5(E-937.65))^{3/2} + 2.7 (50) (E-937.8) (0.5(E-937.8))^{3/2} \\ & + 2.7 (83.3) (E-937.9) (0.5(E-937.9))^{3/2} \end{aligned}$$

$$\begin{aligned} \text{for stage of } 939: Q = & 2.7 (60) (E-938.8) (0.5(E-938.8))^{3/2} + 2.7 (45) (E-938.1) (0.5(E-938.1))^{3/2} \\ & + 2.7 (50) (E-937.5) (0.5(E-937.5))^{3/2} + 2.7 (50) (E-937.65) (0.5(E-937.65))^{3/2} + 2.7 (50) (E-937.8) (0.5(E-937.8))^{3/2} + 2.7 (50) (E-938.2) (0.5(E-938.2))^{3/2} \end{aligned}$$

JOB NO.

SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
1/4 IN. SCALE


$$\begin{aligned} \text{for a stage of } 939.5 : Q &= 2.7 (30) (E-939.05)^{3/2} + 2.7 (45) (E-939.1)^{3/2} \\ &+ 2.7 (50) (E-937.5)^{3/2} + 2.7 (50) (E-937.65)^{3/2} + 2.7 (50) (E-937.8)^3 \\ &+ 2.7 (50) (E-938.2)^{3/2} \end{aligned}$$

Side Slopes (sections D and E): $C = 2.6$ for 927.2-938.5, $Q = 0$

$$\text{for } 939.0 \quad Q = 2.6 (15) (E-938.5) (0.5(E-938.5))^{3/2}$$

$$\text{for } 939.5 \quad Q = 2.6 (5) (E-939.3) (0.5(E-939.3))^{3/2} + 2.6 (15) (E-938.5) (0.5(E-938.5))^{3/2}$$

Elevation (ft. above MGLVD)	Description	Q_{spillway} (cfs)	$Q_{\text{top of dam}}$ (cfs)	$Q_{\text{side slopes}}$ (cfs)	Q_{total} (cfs)
927.2	invert of blow-off, 0 storage	0	0	0	0
935.7	spillway crest	0	0	0	0
936.0		15	0	0	15
936.5		66	0	0	66
937.0		137	0	0	137
937.4	top of dam	205	0	0	205
938.0		323	97	0	420
938.5		372	381	0	753
939.0		432	839	2	1,273
939.5		518	1,447	14	1,979



JOB NO.


SQUARES
1/4 IN. SCALE

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30

Stage vs. Storage

Surface area at normal pool, 935.7 ft NGVD = 14.3 acres. The surface area at 940 ft. NGVD = 20.1 ac. Assume: 4 ft avg. depth (\rightarrow normal storage = $4(14.3) = 57.2$ ac-ft); 0 storage at 927.2; linear increase in surface area with elevation


Elevation (Ft. above NGVD)	ΔH (Feet)	Surface Area (Acres)	Avg. S. A. (Acres)	Incremental Storage (Ac-Ft)	Cumulative Storage (Ac-Ft)
927.2		0			0
	8.5		—	—	
935.7		14.3			57.2
	0.3		14.5	4.4	
936.0		14.7			61.6
	0.5		15.05	7.5	
936.5		15.4			69.1
	0.5		15.7	7.8	
937.0		16.0			76.9
	0.4		16.35	6.5	
937.4		16.7			83.4
	0.6		17.05	10.2	
938.0		17.4			93.6
	0.5		17.75	8.9	
938.5		18.1			102.5
	0.5		18.45	9.2	
939.0		18.8			111.7
	0.5		19.1	9.6	
939.5		19.4			121.3



JOB NO.

SQUARES
1/4 IN. SCALE

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30

Overtopping Analysis

JOB NO.

SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
1/4 IN. SCALEDrawdown Time

① Plans show one 12" pipe, invert at 927.2. Assume inlet control,

$$Q = C A \sqrt{2g} \sqrt{H}; \quad C = 0.61, \quad A = \frac{\pi}{4}, \quad H = E - 927.2$$

$$Q = 0.61 \left(\frac{\pi}{4} \right) \sqrt{64.4} (E - 927.2)^{1/2} = 3.84 (E - 927.2)^{1/2}$$

② For storage below the water surface, assume:

$$S = C_s h^N. \quad h = \text{height above } \phi \text{ storage, } 927.2',$$

from p. 8:

E	h	S
---	---	---

Point 1 935.7 8.5 57.2

Point 2 939.5 12.3 121.3

$$\text{so } 121.3 = C_s (12.3)^N$$

$$\ln 121.3 = \ln C_s + N \ln 12.3$$

$$\rightarrow \ln C_s = 4.798 - N (2.510)$$

$$\text{and } 57.2 = C_s (8.5)^N$$

$$\ln 57.2 = \ln C_s + N \ln 8.5$$

substitute for $\ln C_s$ from above.

$$4.047 = 4.798 - N (2.51) + (N) (2.140)$$

$$N = \frac{4.798 - 4.047}{2.51 - 2.14} = 2.03$$

$$\ln C_s = 4.798 - 2.03 (2.51) = -0.297$$

$$\rightarrow C_s = 0.743$$

$$\text{so } S = 0.743 (E - 927.2)^{2.03}$$

$$\text{③ Ac-ft/day} = 1.98 Q_{\text{avg}}$$

$$\text{④ Days} = \frac{\Delta S}{\text{Ac-ft/day}}$$

JOB NO.

SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
1/4 IN. SCALE

Elevation (Ft above UGVD)	Storage (Ac-Ft)	ΔS (Ac-Ft)	Q (CFS)	Q _{AVG} (CFS)	Ac-Ft per Day	Days
935.7	57.2		10.9			
		9.1		10.65	21.1	0.43
935	48.1		10.4			
		11.7		10.0	19.8	0.59
934	36.4		9.6			
		10.1		9.2	18.2	0.55
933	26.3		8.8			
		8.4		8.4	16.6	0.51
932	17.9		8.0			
		6.7		7.5	14.9	0.45
931	11.2		7.0			
		5.2		6.4	12.7	0.41
930	6.0		5.8			
		3.5		5.1	10.1	0.35
929	2.5		4.4			
		2.0		3.25	6.4	0.31
928	0.5		2.1			
		0.5		1.05	2.1	0.24
927.2	0.0		0			

 $\Sigma = 3.84 \text{ days}$

APPENDIX 4

HEC-1 OUTPUT

CARPI LAKE DAM

LINE	10	1	2	3	4	5	6	7	8	9	10
1	10	CARPI LAKE DAM									
2	10	NEW JERSEY DAM NO. 192 - PASSAIC COUNTY - WEST HELFORD TOWNSHIP									
3	10	ONE-HALF PMF FROM 0									
4	10	5									
5	10	FLOW	0.5								
6	10	JR									
7	10	KK	A1	CARPI LAKE INFLOW HYDROGRAPH							
8	10	KM	INFLOW FROM SCS UNIT GRAPH COMPUTATIONS								
9	10	BA	0.28								
10	10	BE	0.9	1	NO	113	123	132			
11	10	BPH	0.1								
12	10	LU	0.387								
13	10	KK	A2	ROUTE INFLOW HYDROGRAPH THROUGH CARPI LAKE							
14	10	RS	57.2	57.2	69.1	76.9	83.4	93.6	102.5	111.7	121.3
15	10	SV	57.2	61.6	69.1	76.9	83.4	93.6	102.5	111.7	121.3
16	10	SE	927.2	935.7	936.5	937.4	937.4	938.5	938.5	939.5	939.5
17	10	SE	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2
18	10	SE	927.2	935.7	936.5	937.4	937.4	938.5	938.5	939.5	939.5
19	10	SE	935.7	935.7	936.5	937.4	937.4	938.5	938.5	939.5	939.5
20	10	SE	275.0	275.0	275.0	275.0	275.0	275.0	275.0	275.0	275.0
21	10	SE	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
22	10	SE	937.4	937.4	938.5	938.5	939.5	939.5	939.5	939.5	939.5

 * U.S. ARMY CORPS OF ENGINEERS
 * THE HYDROLOGIC ENGINEERING CENTER
 * 609 SECOND STREET
 * DAVIS, CALIFORNIA 95616
 * (916) 440-3285 OR (FIS) 448-3285
 * *****

 * FLOOD HYDROGRAPH PACKAGE (HEC-1)
 * FEBRUARY 1981
 *
 * RUN DATE 06/30/81 TIME 14.21.50
 * *****

CARPI LAKE DAM NO. 192 - PASSAIC COUNTY - WEST MILFORD TOWNSHIP
 NEW JERSEY
 ONE-HALF PMF FROM 24-HOUR PMF

5 IO OUTPUT CONTROL VARIABLES
 PRINT CONTROL 1
 PLOT CONTROL 1
 HYDROGRAPH PLOT SCALE 0
 PRINT DIAGNOSTIC MESSAGES YES

IT HYDROGRAPH TIME DATA 5 MINUTES IN COMPUTATION INTERVAL
 INKIN 1 0 STARTING DATE
 IYIME 1 0000 STARTING TIME
 NO 300 NUMBER OF HYDROGRAPH ORDINATES
 NODATE 2 0055 ENDING DATE
 NUTIME 0055 ENDING TIME
 COMPUTATION INTERVAL 0.08 HOURS
 TOTAL TIME BASE 24.92 HOURS

ENGLISH UNITS
 ORAINAGE AREA SQUARE MILES
 PRECIPITATION DEPTH INCHES
 LENGTH ELEVATION FEET
 FLOW RATE CUBIC FEET PER SECOND
 STORAGE VOLUME ACRES-Feet
 SURFACE AREA ACRES
 TEMPERATURE DEGREES FAHRENHEIT

JP MULTI-PLAN OPTION 1 NUMBER OF PLANS
 JR MULTI-RATIO OPTION
 RATIOS OF RUNOFF 0.50

7 KK CARPI LAKE INFLOW HYDROGRAPH
 INFLOW FROM SCS UNIT GRAPH COMPUTATIONS

9 BA SUBBASIN CHARACTERISTICS
 AREA 0.24 SUBBASIN AREA

10 RF BASE FLOW CHARACTERISTICS
 STRTO 0.90 INITIAL FLOW
 URCSN 0.90 BEGIN RASIN FLOW RECESSON
 RTIOR 1.00000 RECESSON CONSTANT

PRECIPITATION DATA

11 PM PROBABLE MAXIMUM STORM INDEX PRECIPITATION
 TRSPC 22.00 TRANSPOSITION COEFFICIENT
 TRSDA 0.00 TRANSPOSITION AREA
 SHD 0.00 USE SMO DISTRIBUTION

PERCENT OF INDEX PRECIPITATION OCCURRING IN GIVEN TIME
 12 HR 123.0 24-HR 132.0 48-HR 0.0 72-HR 0.0 96-HR 0.0

12 LU UNIFORM LOSS RATE 1.00 INITIAL LOSS RATE
 STRL 0.10 UNIFORM LOSS RATE
 CNSTL 0.0 PERCENT IMPERVIOUS AREA
 RTIMP

13 UD SCS DIMENSIONLESS UNITGRAPH LAG
 LAG 0.39

UNIT HYDROGRAPH
 25 END-OF-PERIOD ORDINATES
 30: 94: 198: 286: 315: 300: 256: 194: 134: 97:
 72: 53: 38: 28: 20: 15: 11: 18: 6: 4:
 3: 2: 2: 1: 0:

HYDROGRAPH AT STATION A1

DA	MON	HRMN	ORD	RAIN	LOSS	EXCESS	COMP Q	DA	MON	HRMN	ORD	RAIN	LOSS	EXCESS	COMP Q
1	0000	1	0.0	0.0	0.0	1:	1	1230	151	0.17	0.01	0.16	0.01	0.16	209:
1	0005	2	0.01	0.01	0.00	1:	1	1235	152	0.17	0.01	0.16	0.01	0.16	245:

.....
.....
.....

.....
.....
.....

.....
.....
.....

.....
.....
.....

.....
.....
.....

.....
.....
.....

.....

.....

.....
.....
.....

.....
.....
.....

.....
.....
.....

.....
.....
.....

.....
.....
.....

.....
.....
.....

.....

PEAK FLOW (CFS)	TIME (HR)	6-HR (CFS)	MAXIMUM AVERAGE FLOW	24.92-HR
1771.	15.92	570	72-HR 150	150
		18.91	20.675	20.675
		283.	309.	309.
CUMULATIVE AREA =			0.28 SQ MI	

CUMULATIVE AREA = 0.28 SQ MI

HYDROGRAPH AT STATION
PLAN 1, 0.50 A1

CA	HRMY	ORD	FLOW	DA	MON	HRMN	ORD	FLOW	DA	MON	HRMN	ORD	FLOW	DA	MON	HRMN	ORD	FLOW	DA	MON	HRMN	ORD	FLOW	DA	MON	HRMN	ORD	FLOW
00	00	1	00	1	00	0615	76	00	1	00	0615	1523	04	1	00	0615	1523	04	1	00	0615	1523	1	00	0615	1523	04	
00	00	2	00	1	00	0620	77	00	1	00	0620	1524	12	1	00	0620	1524	12	1	00	0620	1524	1	00	0620	1524	12	
00	00	3	00	1	00	0625	78	00	1	00	0625	1525	13	1	00	0625	1525	13	1	00	0625	1525	1	00	0625	1525	13	
00	00	4	00	1	00	0630	79	00	1	00	0630	1526	14	1	00	0630	1526	14	1	00	0630	1526	1	00	0630	1526	14	
00	00	5	00	1	00	0635	80	00	1	00	0635	1527	15	1	00	0635	1527	15	1	00	0635	1527	1	00	0635	1527	15	
00	00	6	00	1	00	0640	81	00	1	00	0640	1528	16	1	00	0640	1528	16	1	00	0640	1528	1	00	0640	1528	16	
00	00	7	00	1	00	0645	82	00	1	00	0645	1529	17	1	00	0645	1529	17	1	00	0645	1529	1	00	0645	1529	17	
00	00	8	00	1	00	0650	83	00	1	00	0650	1530	18	1	00	0650	1530	18	1	00	0650	1530	1	00	0650	1530	18	
00	00	9	00	1	00	0655	84	00	1	00	0655	1531	19	1	00	0655	1531	19	1	00	0655	1531	1	00	0655	1531	19	
00	00	0	00	1	00	0700	85	00	1	00	0700	1532	20	1	00	0700	1532	20	1	00	0700	1532	1	00	0700	1532	20	
00	00	1	00	1	00	0705	86	00	1	00	0705	1533	21	1	00	0705	1533	21	1	00	0705	1533	1	00	0705	1533	21	
00	00	2	00	1	00	0710	87	00	1	00	0710	1534	22	1	00	0710	1534	22	1	00	0710	1534	1	00	0710	1534	22	
00	00	3	00	1	00	0715	88	00	1	00	0715	1535	23	1	00	0715	1535	23	1	00	0715	1535	1	00	0715	1535	23	
00	00	4	00	1	00	0720	89	00	1	00	0720	1536	24	1	00	0720	1536	24	1	00	0720	1536	1	00	0720	1536	24	
00	00	5	00	1	00	0725	90	00	1	00	0725	1537	25	1	00	0725	1537	25	1	00	0725	1537	1	00	0725	1537	25	
00	00	6	00	1	00	0730	91	00	1	00	0730	1538	26	1	00	0730	1538	26	1	00	0730	1538	1	00	0730	1538	26	
00	00	7	00	1	00	0735	92	00	1	00	0735	1539	27	1	00	0735	1539	27	1	00	0735	1539	1	00	0735	1539	27	
00	00	8	00	1	00	0740	93	00	1	00	0740	1540	28	1	00	0740	1540	28	1	00	0740	1540	1	00	0740	1540	28	
00	00	9	00																									

```

*****
14 KK *****
*
* A2 *
*
*****
15 RS *****
*
* STORAGE ROUTING
* HSTYP
* KSVNIC
*
*****

```

```

*****
PEAK FLOW (CFS) 886.
TIME (HR) 15.92
(CFS) (INCHES) (AC-FT)
6-HR 24-HR MAXIMUM AVERAGE FLOW
94.5 78 72.5 24.92-HR
141. 154. 10.337 10.337
CUMULATIVE AREA = 0.28 SQ MI
*****

```

```

*****
ROUTE INFLOW HYDROGRAPH THROUGH CARPI LAKE
*****
HYDROGRAPH ROUTING DATA
*****
STORAGE ROUTING
HSTYP
KSVNIC
*****
1 NUMBER OF SURREACHES
STOR TYPE OF INITIAL CONDITION
57.20 INITIAL CONDITION
0.0 WORKING R AND U COEFFICIENT
*****

```

16 SW	STORAGE	0.0	57.2	61.6	69.1	76.9	83.4	93.6	102.5	111.7	121.3
17 SE	ELEVATION	927.20	935.70	936.00	936.50	937.00	937.40	938.00	938.50	939.00	939.50
18 SW	DISCHARGE	0.	0.	15.	66.	137.	205.	420.	753.	1273.	1979.
19 SE	ELEVATION	927.20	935.70	936.00	936.50	937.00	937.40	938.00	938.50	939.00	939.50

TOP OF DAM	TOP OF DAM	ELEVATION AT TOP OF DAM
DAM HEAD	275.00	DAM HEAD COEFFICIENT
DAM CROWN	0.00	WEIGHT OF HEAD
DAM EXPOSED	1.50	

	COMPUTED STORAGE-OUTFLOW CURVE				
STORAGE	0.0	57.20	61.60	69.10	83.40
				93.60	102.50
					111.70
					121.30
OUTFLOW	0.0	0.0	15.00	66.00	137.00
				205.00	420.00
					753.00
					1273.00
					1979.00

[illegible]

[illegible]

1	0755	99	1.	57.5	935.7	*	1	1615	196	645.	99.6	938.3	*	3	0035	299	12.	60.7	935.9
1	0800	98	1.	57.6	935.7	*	1	1620	197	648.	98.9	938.3	*	3	0040	298	12.	60.6	935.9
1	0805	98	2.	57.7	935.7	*	1	1625	198	540.	97.9	938.2	*	3	0045	298	11.	60.5	935.9
1	0810	99	2.	57.8	935.7	*	1	1630	199	538.	96.8	938.1	*	2	0050	299	11.	60.5	935.9
1	0815	100	2.	57.9	935.7	*	1	1635	200	496.	95.6	938.1	*	2	0055	300	11.	60.5	935.9

PEAK OUTFLOW IS 652. AT TIME 16.17 HOURS

PEAK FLOW (CFS) 652.	TIME (HR) 16.17	6-HR 260. 8619 129.	MAXIMUM AVERAGE FLOW 72-HR 73 10.081 151.	24.92-HR 73 10.081 151.
EAK STORAGE (AC-FT) 100.	TIME (HR) 16.17	6-HR 84.	MAXIMUM AVERAGE STORAGE 72-HR 66. 66.	24.92-HR 66. 66.
PEAK STAGE (FEET) 958.35	TIME (HR) 16.17	6-HR 937.28	MAXIMUM AVERAGE STAGE 72-HR 936.25 936.25	24.92-HR 936.25 936.25
CUMULATIVE AREA = 0.28 SQ MI				

RATIOS APPLIED TO FLOWS

OPERATION	STATION	AREA	PLAN	RATIO
HYDROGRAPH-A1	A1	0.28	1 FLOW TYPE	886 15.92
	A2	0.28	1 FLOW	652 16.14
ROUTED TO			** PEAK STAGES IN FEET	**
			1 STAGE	938.35
			1 TYPE	16.17

SUMMARY OF DAM OVERTOPPING/BREACH ANALYSIS FOR STATION A2

PLAN 1	ELEVATION STORAGE OUTFLOW	INITIAL VALUE 935.70 0.	SPILLWAY CREST 935.70 0.	TOP OF DAM 937.80 205.	DURATION OVER TOP HOURS	MAXIMUM OUTFLOW CFS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
RATIO OF PHF	MAXIMUM RESERVOIR H.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FY					
0.50	938.35	0.95	100.		3.08	652.	16.17	0.0

*** NORMAL END OF JOB ***

.....7.....8.....9.....10

[illegible]

ID. ID ID ID ID KKH KKH KKH KKH KKH
ID ID ID ID ID KKH KKH KKH KKH KKH
ID ID ID ID ID KKH KKH KKH KKH KKH

[illegible]

 FLOOD HYDROGRAPH PACKAGE (HFC-1)
 FEBRUARY 1981
 RUN DATE 08/10/81 TIME 10.43.37

 U.S. ARMY CORPS OF ENGINEERS
 THE HYDROLOGIC ENGINEERING CENTER
 609 SECOND STREET
 DAVIS, CALIFORNIA 95616
 (916) 440-3285 OR (FIS) 448-3285

CARPI LAKE DAM OVERTOPPING ANALYSIS TOM COUCH ANCO
 NEW JERSEY DAM NO. 192 - PASSAIC COUNTY - WEST MILFORD TOWNSHIP
 0.1-0.25-0.5 MULTIPLES OF PHF FROM 24-HOUR PHF

5 10 OUTPUT CONTROL VARIABLES
 PRINT 3
 PLOT 0
 SCALE 0
 YES PRINT DIAGNOSTIC MESSAGES

17 HYDROGRAPH TIME DATA
 MIN 5
 DATE 1
 TIME 0000
 NO 300
 NUMBER OF HYDROGRAPH ORDINATES
 NO DATE 2
 ENDING TIME 0055

COMPUTATION INTERVAL 3.04 HOURS
 TOTAL TIME BASE 24.92 HOURS

ENGLISH UNITS
 DRAINAGE AREA DEPTH
 PRECIPITATION INCHES
 FLOW CUM. ELEVATION FEET
 STORAGE VOLUME CUBIC FEET PER SECOND
 SURFACE AREA ACRES
 TEMPERATURE DEGREES FAHRENHEIT

JP MULTI-PLAN OPTION 1 NUMBER OF PLANS
 JR MULTI-RATIO OPTION 0.50
 RATIOS OF RUNOFF 0.10

 7 KK CARPI LAKE INFLOW HYDROGRAPH

INFLOW FROM SCS UNIT GRAPH COMPUTATIONS

SURBASIN RUNOFF DATA

9 BA SURBASIN CHARACTERISTICS
 AREA 0.28 SUBBASIN AREA

10 BF BASE FLOW CHARACTERISTICS
 START 0.50 INITIAL FLOW
 GPCSN 0.28 BEGIN BASF FLOW REVERSION
 RTIOR 1.00000 REVERSION CONSTANT

PRECIPITATION DATA

11 PM PROBABLE MAXIMUM STORM
 PMS 22.00 INDEX PRECIPITATION
 TRSDC 0.50 TRANSDITION COEFFICIENT
 TRSCA 0.28 TRANSDITION AREA
 SMD USE SMD DISTRIBUTION

PERCENT OF INDEX PRECIPITATION OCCURRING IN GIVEN TIME
 6-HR 12-HR 24-HR 48-HR 72-HR 96-HR
 111.0 123.0 133.0 0.0 0.0 0.0

12 LU UNIFORM LOSS RATE

1.00 INITIAL LOSS RATE
 0.10 UNIFORM LOSS RATE
 0.0 PERCENT IMPERVIOUS AREA

13 UD SCS DIMENSIONLESS UNITGRAPH
 FLAG 0.39 LAG

UNIT HYDROGRAPH
 25 END-OF-PERIOD ORDINATES
 315. 300. 256. 11. 97. 4.
 20. 15. 6. 134. 194. 134. 97.

94. 198. 286. 315. 300. 256. 11. 97. 4.
 53. 38. 28. 20. 15. 6. 134. 194. 134. 97. 4.
 2. 2. 1. 1. 1. 1. 1. 1. 1. 1. 1.

PEAK FLOW
 (CFS)
 1740.

TIME
 (HR)
 15.92

(CFS) 6-HR 24-HR 72-HR 24.92-HR
 (INCHES) 18.282 560. 151. 151.
 (AC-FT) 277. 20.804 20.808 20.311.

CUMULATIVE AREA = 0.28 SQ MI

HYDROGRAPH AT STATION A1
 FOR PLAN 1. RATIO = 0.10

PEAK FLOW
 (CFS)
 174.

TIME
 (HR)
 15.92

(CFS) 6-HR 24-HR 72-HR 24.92-HR
 (INCHES) 1.858 56. 15. 15.
 (AC-FT) 28. 2.080 2.081 2.031.

CUMULATIVE AREA = 0.28 SQ MI

HYDROGRAPH AT STATION A1
 FOR PLAN 1. RATIO = 0.25

PEAK FLOW
 (CFS)
 435.

TIME
 (HR)
 15.92

(CFS) 6-HR 24-HR 72-HR 24.92-HR
 (INCHES) 4.645 140. 39. 38.
 (AC-FT) 89. 5.201 5.202 5.202.

CUMULATIVE AREA = 0.28 SQ MI

HYDROGRAPH AT STATION A1
 FOR PLAN 1. RATIO = 0.50

PEAK FLOW
 (CFS)
 870.

TIME
 (HR)
 15.92

(CFS) 6-HR 24-HR 72-HR 24.92-HR
 (INCHES) 9.291 280. 78. 75.
 (AC-FT) 139. 10.402 10.404 10.404.

CUMULATIVE AREA = 0.28 SQ MI

*** ** ** ** **

A2

ROUTE INFLOW HYDROGRAPH THROUGH CARPI LAKE

HYDROGRAPH ROUTING DATA

| 14 RK | STORAGE ROUTING
NTYPE
RSVRIC | STOR
TYPE OF INITIAL
CONDITION
57.20
0.0 WORKING R AND O COEFFICIENT | 1
NUMBER OF SUBREACHES
TYPE OF INITIAL
CONDITION
57.20
0.0 WORKING R AND O COEFFICIENT | 16 SV | STORAGE | 0.0 | 57.2 | 61.6 | 69.1 | 76.9 | 83.4 | 93.6 | 102.5 | 111.7 | 121.3 |
|-------|------------------------------------|--|---|-------|-----------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| 15 KS | | | | 17 SE | ELEVATION | 927.20 | 935.70 | 936.00 | 936.50 | 937.00 | 937.40 | 938.00 | 938.50 | 939.00 | 939.50 |
| 18 SO | | | | 18 SO | DISCHARGE | 0. | 0. | 15. | 66. | 137. | 205. | 420. | 753. | 1273. | 1979. |
| 19 SE | | | | 19 SE | ELEVATION | 927.20 | 935.70 | 936.00 | 936.50 | 937.00 | 937.40 | 938.00 | 938.50 | 939.00 | 939.50 |

20 SS
SPILLWAY
CREL
SPWD
CDOW
EXPW

21 ST
TOP OF DAM
TOPEL
DAMWD
CDOD
EXPD

| STORAGE | 0.0 | 57.20 | 61.60 | 69.10 | 76.90 | 83.40 | 93.60 | 102.50 | 111.70 | 121.30 |
|---------|-----|-------|-------|-------|--------|--------|--------|--------|---------|---------|
| OUTFLOW | 0.0 | 0.0 | 15.00 | 66.00 | 137.00 | 205.00 | 420.00 | 753.00 | 1273.00 | 1979.00 |

HYDROGRAPH AT STATION
FOR PLAN 1. RATIO = 0.10 A2

PEAK OUTFLOW IS 74. AT TIME 16.50 HOURS

PEAK FLOW (CFS) 74. TIME (HR) 16.50
(INCHES) 1.521
(AC-FT) 23.
6-HR 46.
24-HR 15.
MAXIMUM AVERAGE FLOW 24.92-HR 14.
72-HR 14.
1.951
1.951
1.29.

PEAK STORAGE
 (AC-FI)
 70.
 TIME
 (HR)
 16.50
 PEAK STAGE
 (FLEI)
 936.56
 TIME
 (HR)
 16.50
 MAXIMUM AVERAGE STORAGE
 24-HR 60.
 72-HR 60.
 MAXIMUM AVERAGE STAGE
 24-HR 935.89
 72-HR 935.88
 CUMULATIVE AREA = 0.28 SQ MI

HYDROGRAPH AT STATION A2
 FOR PLAN I. RATIO = 0.25

PEAK OUTFLOW IS 227. AT TIME 16.33 HOURS

PEAK FLOW
 (CFS)
 227.
 TIME
 (HR)
 16.33
 (INCHES)
 (AC-FI)
 6-HR 122.
 24-HR 38.
 72-HR 36.
 5.000
 5.000
 75.
 75.
 MAXIMUM AVERAGE FLOW
 24-HR 38.
 72-HR 36.
 5.000
 5.000
 75.
 75.
 MAXIMUM AVERAGE STORAGE
 24-HR 63.
 72-HR 63.
 5.000
 5.000
 75.
 75.
 CUMULATIVE AREA = 0.28 SQ MI

PEAK STORAGE
 (AC-FI)
 84.
 TIME
 (HR)
 16.33
 PEAK STAGE
 (FLEI)
 937.46
 TIME
 (HR)
 16.33
 MAXIMUM AVERAGE STORAGE
 24-HR 63.
 72-HR 63.
 5.000
 5.000
 75.
 75.
 MAXIMUM AVERAGE STAGE
 24-HR 936.08
 72-HR 936.07
 CUMULATIVE AREA = 0.28 SQ MI

HYDROGRAPH AT STATION A2
 FOR PLAN I. RATIO = 0.50

PEAK OUTFLOW IS 637. AT TIME 16.17 HOURS

PEAK FLOW
 (CFS)
 637.
 TIME
 (HR)
 16.17
 (INCHES)
 (AC-FI)
 6-HR 256.
 24-HR 76.
 72-HR 73.
 10.133
 10.133
 151.
 151.
 MAXIMUM AVERAGE FLOW
 24-HR 76.
 72-HR 73.
 10.133
 10.133
 151.
 151.
 MAXIMUM AVERAGE STORAGE
 24-HR 67.
 72-HR 66.
 5.000
 5.000
 75.
 75.
 CUMULATIVE AREA = 0.28 SQ MI

PEAK STORAGE
 (AC-FI)
 99.
 TIME
 (HR)
 16.17
 PEAK STAGE
 (FLEI)
 938.33
 TIME
 (HR)
 16.17
 MAXIMUM AVERAGE STORAGE
 24-HR 67.
 72-HR 66.
 5.000
 5.000
 75.
 75.
 MAXIMUM AVERAGE STAGE
 24-HR 936.29
 72-HR 936.27
 CUMULATIVE AREA = 0.28 SQ MI

PEAK FLOW AND STAGE (END-OF-PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND, AREA IN SQUARE FEET
 TIME TO PEAK IN HOURS

| OPERATION | STATION | AREA | PLAN | RATIOS APPLIED TO FLOWS | | |
|----------------------------|---------------------------|------|------|-------------------------|---------|---------|
| | | | | RATIO 1 | RATIO 2 | RATIO 3 |
| HYDROGRAPH AT
ROUTED TO | A1 | 0.28 | 1 | 0.10 | 0.25 | 0.50 |
| | | | | 174 | 435 | 870 |
| | | | | 15.92 | 15.92 | 15.92 |
| | A2 | 0.28 | 1 | 74 | 227 | 637 |
| | | | | 16.50 | 16.33 | 16.17 |
| | ** PEAK STAGES IN FEET ** | | | | | |
| | | | 1 | 936.56 | 937.45 | 938.33 |
| | | | | 16.50 | 16.33 | 16.17 |

SUMMARY OF DAM OVERTOPPING/BREACH ANALYSIS FOR STATION A2

PLAN 1

| ELEVATION
STORAGE
OUTFLOW | INITIAL VALUE | SPILLWAY CREST | TOP OF DAM | DURATION
OVER TOP
HOURS | MAXIMUM
OUTFLOW
CFS | TIME OF
MAX. OUTFLOW
HOURS | TIME OF
FAILURE
HOURS |
|---------------------------------|---------------|----------------|------------|-------------------------------|---------------------------|----------------------------------|-----------------------------|
| | 935.70 | 935.70 | 937.40 | | | | |
| | 57. | 57. | 83. | | | | |
| | 0. | 0. | 205. | | | | |

RATIO
OF
PMF

0.10
0.25
0.50

MAXIMUM
RESERVOIR
W.S. ELEV

936.56
937.26
938.33

MAXIMUM
DEPTH
OVER DAM

0.0
0.06
0.93

MAXIMUM
STORAGE
AC-FT

70.
84.
99.

MAXIMUM
OUTFLOW
CFS

74.
227.
637.

DURATION
OVER TOP
HOURS

0.0
0.58
3.00

TIME OF
MAX. OUTFLOW
HOURS

16.50
16.33
16.17

TIME OF
FAILURE
HOURS

0.0
0.0
0.0

*** NORMAL END OF JOB ***

APPENDIX 5

REFERENCES

CARPI LAKE DAM

APPENDIX 5
REFERENCES

CARPI LAKE DAM

Chow, Ven-Te, Open Channel Hydraulics, McGraw Hill Book Company, New York, 1959.

King, H.W. and E.F. Brater, Handbook of Hydraulics, McGraw Hill Book Company, New York, Fifth Edition 1963.

Kummel, H.B. and Peet Glacial Drift Map of New Jersey, 1902.

Lewis, J.V. and H.B. Kummel (1910-1912) Geologic Map of New Jersey, revised by H.B. Kummel, 1931, and by M.E. Johnson, 1950. New Jersey Department of Conservation of Economic Development Atlas.

Schway, G.O., R.K. Frevert, T.W. Edmister, and K.K. Barnes, Soil and Water Conservation Engineering, The Ferguson Foundation Agricultural Engineering Series, John Wiley and Sons, Inc., New York, 1966, 683 pp.

U.S. Army Corps of Engineers, Hydrologic Engineering Center, Flood Hydrograph Package (HEC-1) Users Manual Preliminary, Davis, California, March 1981.

U.S. Department of Agriculture, Soil Conservation Service, Urban Hydrology for Small Watersheds, Technical Release No. 55, Washington, 1975.

U.S. Department of Commerce, Weather Bureau, "Seasonal Variation of the Probable Maximum Precipitation East of the 105th Meridian for Areas from 10 to 1000 Square Miles and Durations of 6, 12, 24, and 48 Hours", Hydrometeorological Report No. 33, Washington, 1977, 816 pp.

United States Department of Interior, Bureau of Reclamation, Design of Small Dams, U.S. Government Printing Office, Washington, 1977, 816 pp.

U.S. Department of Interior, Geological Survey, 7.5-Minute Series (topographic) maps, scale 1:24000, Contour Interval 10 feet: Wanaque, New Jersey, (1954).

Viessman, Warren, Jr., J.W. Knapp, G.L. Lewis, T.E. Harbaugh, Introduction to Hydrology, Harper and Row, Publishers, New York, Second Edition 1977, 704 pp.

LMED
-8